



STATE BANK OF PAKISTAN  
SBP BANKING SERVICES CORPORATION

---

PROVIDING, FIXING & REPLACEMENT OF FIBERGLASS SHEDS AT VARIOUS PLACES INSIDE  
BANK BUILDING AT SBP BSC ISLAMABAD

---

BIDDING AND CONTRACT DOCUMENT

VOLUME-II

FINANCIAL BID

JULY 2022



## SCHEDULE-A TO BID

### Financial Bid/ Schedule of Prices

#### PROVIDING, FIXING & REPLACEMENT OF FIBERGLASS SHEDS AT VARIOUS PLACES INSIDE BANK BUILDING AT SBP BSC ISLAMABAD

#### 1. PREAMBLE


- i. The items mentioned in Bill of Quantities consist of furnishing all plants, labour, equipment, machinery appliances, materials, fittings, fixtures and fabrication, erection, installation, lifting of materials required for completing the items/works and the work shall be done in accordance with Bill of Quantities, specifications and drawings complete in all respects.
- ii. The quantities contained in the Bill of Quantities are approximate estimated quantities and liable to be changed (increased/decreased) or omitted when the work will be actually executed. The Employer is authorized to delete any item of work or vary quantities of any item(s) of Bill of Quantities. No claim for any adjustment in the unit rate set forth in the Bill of Quantities will be made because of any increase or any decrease in the quantities indicated herein.
- iii. The prices and rates to be quoted in the Bill of Quantities are to be the full inclusive value of the works described under specified items including all cost of expenses which may be required in and for the construction of the works described and implied in all the documents referred to on which the tender is based.
- iv. Rates quoted should be inclusive of all applicable taxes, duties, levies etc.
- v. Unit rate is to be entered against each item in the Bill of Quantities whether quantities are entered or not. Items against which no price or rate is quoted in the Bill of Quantities shall be deemed to have been covered by rates or prices quoted in the other BOQ item.
- vi. Sub-total/Total amounts shall also be referred in words.
- vii. Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern, and the line total will be corrected accordingly.
- viii. Each cutting should be signed by the authorized person.
- ix. The brand names have been provided in order to establish a standard of performance and reliability. However, it does not indicate a preference for a particular brand. The bidder may propose other brands, which can be accepted subject to necessary tests to establish equivalency at bidder's cost.



**BILL OF QUANTITIES:**

S #	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Removal/dismantling of existing fiberglass sheet from over the shed located in front of annexe building inside Bank premises, handing over the serviceable removed materials to the Bank and stacking the same at designated location within the Bank premises and disposal of debris away from the Bank premises, complete in all respects as per site requirements and as directed by the Engineer In-Charge. (Quantity is based on removal of each individual unit of varying size)	Jobs	03		
2	Providing and fixing; a) over the existing trusses and purlins, fiberglass sheet of at least 2mm thickness (3-ply) of FiberTech or approved equivalent/Tensile fabric of approved thickness and shade make as per site requirements, specifications including overlaps where required, riveting etc. complete in all respects. c) Providing and applying paint to all structural steel sections, one coat of red oxide primer and three coats of approved colour enamel paint of Nippon or approved equivalent make, complete in all respects as directed by the Engineer In-Charge. Note: Measurement for payments shall be made on the basis of the projected plan area of the shade over the ground, no adjustment will be considered regarding curvature or overlaps etc.	Sft	650		
3	Providing, fabricating, erection and fixing in position, fiberglass shed over MS trusses as per the drawings, and as directed by the Engineer In-Charge, including the following; a) Providing, fabricating and fixing in position structural steel framing for shed comprising of the MS square pipe of 1-1/2" x 1-1/2" with the adjacent walls as shown in drawings using rawl bolts of about 10mm dia throughout the length at considerable distance to provide a cantilever support, painting of MS pipes with one coat of approved quality red oxide primer and minimum three coats of approved quality enamel paint of NIPPON or other approved equivalent make, welding works to connect MS pipes, making of holes in any type of walls/beams/columns etc. for fixing of rawl bolts, complete in all respects as per site requirements and as directed by the Engineer In-Charge.	Sft	400		

For Contractor (Sign and Seal)




(Bank) Islamabad

S #	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	<p>b) Providing and fixing over the trusses and purlins, fiberglass sheet of at least 3mm thickness (3-ply) of FiberTech or approved equivalent/Tensile Fabric of approved shade and thickness as per the drawings, specifications including overlaps where required, riveting etc. complete in all respects.</p> <p>Note: Measurement for payments shall be made on the basis of the projected plan area of the shade over the ground, no adjustment will be considered regarding curvature or overlaps etc.</p>				
4	<p>Providing, fabricating, erection and fixing in position, fiberglass shed over MS trusses as per the drawings, and as directed by the Engineer In-Charge, including the following;</p> <p>a) Providing, fabricating and fixing in position structural steel framing comprising of main longitudinal trusses provided at both ends and transverse trusses provided at both shorter ends in continuation to existing truss upto required length, including welding/connecting the main &amp; side trusses with vertical supports as per existing design including the required cleats, steel plates at top of pipe supports, grinding of welds for smooth &amp; fair surface, complete in all respects as per drawings, specifications and as directed by the Engineer In-Charge.</p> <p>b) Providing and fixing over the trusses and purlins, fiberglass sheet of at least 3mm thickness (3-ply) of FiberTech or approved equivalent/Tensile fabric of required thickness and shade as per the drawings, specifications including overlaps where required, riveting etc. complete in all respects.</p> <p>c) Providing and applying paint to all structural steel sections, one coat of red oxide primer and three coats of approved colour enamel paint of ICI Dulux or approved equivalent make, complete in all respects as directed by the Engineer In-Charge.</p> <p>Note: Measurement for payments shall be made on the basis of the projected plan area of the shade over the ground, no adjustment will be considered regarding curvature or overlaps etc.</p>	Cft	380		
<b>TOTAL AMOUNT (RS.)=</b>					

**Total Amount Rs. (In words)**

For Contractor (Sign and Seal)



**Undertaking by the Bidder:**

I \_\_\_\_\_ had visited the site and have fully understood the scope of work & specifications. The above rates are inclusive of all labor charges, Tool & Plants, applicable taxes/ duties, overheads, safety equipment's/PPEs/measures etc. I/ we have sufficient resources to carry out above works. All the above Terms & Conditions are acceptable to us. We are not blacklisted by the Bank or any other organization.

**Date:**

**Contractors Signature & Seal**

For Contractor (Sign and Seal)



For SBC (Bank) Islamabad