

### STATEBANKOFPAKISTAN

# SBP BANKING SERVICES CORPORATION (BANK)

## **QUETTA**

## Financial Bid

## **Bidding Documents**

For

STRENGTHENING OF INTACT PRECAST WALL COLUMNS AT SBP PLOT KHUZDAR

(Volume-II)

December 2023

#### **SCHEDULE-A TO BID**

#### Financial Bid/Schedule of Prices

#### STRENGTHENING OF INTACT PRECAST WALL COLUMNS AT SBP PLOT KHUZDAR

#### 1. PREAMBLE

- i. The items mentioned in Bill of Quantities consist of furnishing all plants, labour, equipments, machinery appliances, materials, fittings, fixtures and fabrication, erection, installation, lifting of materials required for completing the items/works and the work shall be done in accordance with Bill of Quantities, specifications and drawings complete in all respects.
- ii. The quantities contained in the Bill of Quantities are approximate estimated quantities and liable to be changed (increased/decreased) or omitted when the work will be actually executed. The Employer is authorized to delete any item of work or vary quantities of any item(s) of Bill of Quantities. No claim for any adjustment in the unit rate set forth in the Bill of Quantities will be made because of any increase or any decrease in the quantities indicated herein.
- iii. The prices and rates to be quoted in the Bill of Quantities are to be the full inclusive value of the works described under specified items including all cost of expenses which may be required in and for the construction of the works described and implied in all the documents referred to on which the tender is based.
- iv. Rates quoted should be inclusive of all applicable taxes, duties, levies etc.
- v. Unit rate is to be entered against each item in the Bill of Quantities whether quantities are entered or not. Items against which no price or rate is quoted in the Bill of Quantities shall be deemed to have been covered by rates or prices quoted in the other BOQ item.
- vi. Sub-total/Total amounts shall also be referred in words.
- vii. Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern, and the line total will be corrected accordingly.
- viii. Each cutting should be signed by the authorized person.
- ix. The brand names have been provided in order to establish a standard of performance and reliability. However, it does not indicate a preference for a particular brand. The bidder may propose other brands which can be accepted subject to necessary tests to establish equivalency at bidder's cost.

**BILL OF QUANTITIES:** 

Item No.	Description of Items	Unit	Qty	Rate	Amount		
1	Strengthening of existing pre-cast columns by: removing columns pedestal top concrete about 9" depth then 1. Embedding and erecting 2 nos, 3.5ft long and 1/2" dia steel reinforcement bars upto 6" in the pre-cast column foundation. 2. Providing and placing 3ft long 1.5" x 1.5" x 3/16" MS angle iron at the four corners of the pre-cast columns. 3. Clamping the angle iron by providing and fixing 2 nos 1.5"x3/16" flat iron bars around the column and clamping using nut and bolt mechanism. 4. Column concreting using 1:2:4 concrete from the foundation top (ground level) upto 3ft height, including cost of formwork and curing. Complete in all respects as per drawings, specifications and as directed by the Engineer In-Charge	Nos	150				
TOTAL AMOUNT (RS)=							

Total Amount Rs. (In words)										
Undertaking by the Bidd	er:									
I had visited the site and have fully understood the scope of work & specifications. The above rates are inclusive of all labour charges, Tool & Plants, applicable taxes/duties, overheads, safety equipments/PPEs/measures etc. I/ we have sufficient resources to carry out above works. All the above Terms & Conditions are acceptable to us. We are not blacklisted by the Bank or any other organization.										
Date: Contractors Signature & Seal										
For Official Use only										
		•								
Nos. of cuttings/overwr	iting	Nos. of altera	tions							
Evagutive Engineer	ACM (IMI)			DCM (Admin)						
Executive Engineer	ACM (IMU)	ACM (SMU)	ACM (Bkg)	DCM (Admin)						